Temporary Fence Types List				
Item No.	Pictures	Description	Unit Weight/kgs	Qty In 1x40'HC
DBTF0001		1) 2400mm(L) x 2100mm(H), 32mm O.D. &1.35mm Wall Thickness Galvanised, Φ 3.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	12.94 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0002		1) 2400mm(L) x 2100mm(H), 32mm O.D. &1.2mm Wall Thickness Galvanised, Φ 3.5x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	16.2 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0003		1) 2400mm(L) x 2100mm(H), 32mm O.D. &1.5mm Wall Thickness Galvanised, Φ 3.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	14.94 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0004		1) 2400mm(L) x 2100mm(H), 32mm O.D. &1.4mm Wall Thickness Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	17.8 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0005		1) 2400mm(L) x 2100mm(H), 32mm O.D. &1.6mm Wall Thickness Galvanised, Φ 4.0x60x160 mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm,80mm,90mm,100mm hole spacing(C/C)	20.02 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0006		1) 2400mm(L) x 2100mm(H), 32mm O.D. & 1.8mm vertical frame tube and 32x1.2mm horizontal frame tube Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, ,75mm,80mm,90mm,100mm hole spacing(C/C)	18.3 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0007		1) 2400mm(L) x 2100mm(H), 32mm O.D. & 2.0mm Wall Thickness Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, ,75mm,80mm,90mm,100mm hole spacing(C/C)	23.72 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0008		1) 2400mm(L) x 2100mm(H), 32mm O.D. & 2.0mm Wall Thickness Galvanised, Φ 4.0x60x150mm infill mesh, **Hot dipped galvanised after welding AS4687 -2007 standard** ; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised,75mm,80mm,90mm,100mm hole spacing(C/C)	23.72 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0009		1) 2300mm(L) x 1878mm(H), 32mm O.D. & 2.0mm Wall Thickness Galvanised, 21.3mm O.D. 1.6mm wall thick bracing, Φ 4.0x70x200 mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	19.8 Panel + 26.5-28 Feet + 0.42kgs Clamps	675 sets
DBTF0010		1) 2315mm(L) x 2175mm(H), 32mm O.D. &2.0mm Wall Thickness Galvanised, Φ 2.5x50x50 mm infill chain link mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm, 100mm hole spacing(C/C)	18.5 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0011		1) 2400mm(L) x 2100mm(H), 32mm O.D. &2.0mm Wall Thickness Galvanised, Φ 2.5x50x50 mm infill chain link mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	18.6 Panel + 26.5-28 Feet + 0.42kgs Clamps	550 sets
DBTF0012		2400mm(L) x 2100mm(H), 32mm O.D. &1.35mm Wall Thickness Galvanised, Φ 3.0x60x150mm infill mesh, Pre-Galvanised and zinc painting	12.94	670 pcs
DBTF0013		2400mm(L) x 2100mm(H), 32mm O.D. &1.2mm Wall Thickness Galvanised, Φ 3.5x60x150mm infill mesh, Pre-Galvanised and zinc painting;	16.2	670 pcs
DBTF0014		2400mm(L) x 2100mm(H), 32mm O.D. &1.5mm Wall Thickness Galvanised, Φ 3.0x60x150mm infill mesh, Pre-Galvanised and zinc painting	15.02	670 pcs
DBTF0015		2400mm(L) x 2100mm(H), 32mm O.D. &1.6mm Wall Thickness Galvanised, Φ 4.0x60x160 mm infill mesh, Pre-Galvanised and zinc painting	20.02	670 pcs
DBTF0016		2400mm(L) x 2100mm(H), 32mm O.D. & 1.8mm vertical frame tube and 32x1.2mm horizontal frame tube Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting;	18.8	670 pcs
DBTF0017		2400mm(L) x 2100mm(H), 32mm O.D. & 2.0mm Wall Thickness Galvanised, Φ 4.0x60x150mm infill mesh, **Hot dipped galvanised after welding AS4687 -2007 standard** ;	18.8	670 pcs
DBTF0018		3300mm(L) x 2100mm(H), 32mm O.D. & 2.0mm frame and middle brace tube high zinc Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	29.2	381 sets
DBTF0019		3250mm(L) x 2100mm(H), 32mm O.D. & 2.0mm frame and middle brace tube high zinc Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting;2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	28.9	381 sets
DBTF0020		3000mm(L) x 2100mm(H), 32mm O.D. & 2.0mm frame and middle brace tube high zinc Galvanised, Φ 4.0x60x150mm infill mesh, Pre-Galvanised and zinc painting;2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	27.3	440 sets
DBTF0021		2500mm(L) x 2000mm(H), Vertical frame tube Φ 40mm O.D. & 2.0mm Wall Thickness, and horizontal tube Φ 40 x 2.0mm, Φ 4.0x75x75mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	25.3	500 sets
DBTF0022		2426mm(L) x 2000mm(H), Vertical frame tube Φ 40mm O.D. & 2.0mm Wall Thickness, and horizontal tube Φ 40 x 2.0mm, Φ 4.0x75x75mm infill mesh, Pre-Galvanised and zinc painting; 2) High-density polyethylene feet 610x230x150mm, 26.5-28kgs with concrete; 3) steel clamps: Hot Dipped Galvanised, 75mm, 80mm, 90mm,100mm hole spacing(C/C)	24.64	500 sets